

From
Thiru.P.Ponniah, I.A.S.,
Director,
Rural Development and Panchayat Raj,
Panagal Building,
Saidapet, Chennai-15.

To
The District Collector/Chairman,
District Rural Development Agency,
All Districts

Rc.No.50395/2021/MGNREGS -I-1, Dated.15.09.2023

Sir/Madam,

Sub: Mahatma Gandhi NREGS -Construction of Working Shed for SHGs -Modification in Type Design - Instructions Issued-Reg.

Ref: 1. GO(Ms).No.139 Rural Development (CGS.1) Department, Dated 01.12.2021.
2. This Office Letter No.Rc.No.50395/ 2021/ MGNREGS-I-1, Dt:05.02.2022.

I invite your kind attention to the reference cited.

Government has issued order for the construction of Working Sheds for SHGs to provide common infrastructure facilities in rural areas with the aim to provide proper capacity building development of skill for sustained livelihood activities vide reference cited

The district wise target for 500 Working Shed has been communicated to districts vide reference 2nd cited. As per the model estimate approved in GO, Working Shed should be constructed at a cost of Rs.9.60 Lakh with roofing height of 4.2 meter to place and use the factory/heavy machineries.

However, based on the requirement at field level modification shall be done for the type design and estimate amount communicated with GO. Accordingly, the following instructions are issued.

- The roofing height of 3.6 meter shall be adopted for the activities involving less SHG women like Garments and Jute Bags unit, Aari Works, Flouring Machine Units Weaving unit, Making Bamboo and Wire Basket, Terracotta Toys, Sanitary Napkins, Pot Making, Oil Extracting Units and Handicraft Unit etc.,
- Only for the activities involving heavy machineries with the height 3 meter, the working sheds can be constructed with the roofing height of 4.2 meter.

- Turbo ventilator facilities should be provided in the roof.
- The provision for Toilet facility was not provided in the existing model. Hence, a Mini CSC (Model-2) under SBM may be constructed for the completed and ongoing Sheds based on the need. For the new type designs also Toilets may be taken up under SBM if their available in the District.

However, depending on the number of SHG women/Activity involved in the work the new type design including toilet facility may be followed accordingly as follows.

SHG Working Shed								
S. No	Description	Size of the building in m	Area in Sqm	Area in Sqft	Estimate Amount (in lakhs) for PUF panel roofing	Mandays	Labour: Material ratio	Remarks
1	SHG Working Shed (Existing Model) with toilet	7.96 x 6.46 (26 ft x 21 ft)	67.26	723.72	12.58	315	7.35 : 92.65	for Garments (10 users), Aari work (10 units), Flouring machine Unit, Making bamboo and wire basket, making Terracotta toys and Napkin production unit
2	SHG Working Shed for Aari work (25 Users)	17.46 x 6.16 (57 ft x 20 ft)	113.84	1224.92	20.95	536	7.52 : 92.48	
3	SHG Working Shed for Aari work (50 Users)	20.46 x 8.46 (67ft x 27ft)	181.75	1955.63	29.35	848	8.49 : 91.51	
4	SHG Working Shed for Garments (25 Users)	24.46 x 8.46 (80ft x 27ft)	213.22	2294.25	32.04	946	8.68 : 91.32	
5	SHG Working Shed for Garments (50 Users)	27.46 x 13.06 (90 ft x 42 ft)	367.22	3951.29	71.78	1613	6.60 : 93.40	
6	SHG Working Shed for Oil Extraction Unit	12.46x5.46m (40ft x 17ft)	75.17	808.83	15.78	384	7.14 : 92.86	

Hence I request you that necessary instructions may be issued to the field functionaries to follow the above type designs based on the activity and number of SHG women involvement and to send the proposal for not started sheds for approval of DRD&PR.

Encl:

Type Design and Estimate
for 6 types of SHGs as above.

Sd/- P.Ponniah
Director

-t.c.f.b.o-


Additional Director (MGNREGS)

