

From
Thiru.P.Ponniah, I.A.S.,
Director,
Directorate of Rural Development and
Panchayat Raj,
Panagal Building, Saidapet,
Chennai-15

To
The District Collector / Chairman,
District Rural Development Agency,
All Districts.

Lr.No.41636/2024/MGNREGS-II-2, Dated:26.06.2024

Sir / Madam,

Sub: Mahatma Gandhi NREGS – RD & PR Department –
Announcements made by Hon'ble Minister of Rural
Development Department on the floor of Tamil Nadu
Legislative Assembly on 22.06.2024 – Construction of
School Compound Wall - Works to be taken up under
MGNREGS during the FY 2024-25 – Executive Orders
issued - Regarding.

- Ref :
1. MGNREG Act Schedule I: 2005 Paragraph 4 (1) IV
Category-D
 2. List of 266 approved works.
 3. Annual Master Circular issued by Government of
India, Ministry of Rural Development for the
implementation of MGNREGS 2024-2025.
 4. Minutes of the Empowered Committee meeting of
MoRD, GoI held on 28.03.2024.
 5. Gazette Notification No.S.O.1481 (E),
dated.27.03.2024 issued by MoRD, Government of
India.
 6. G.O.(Ms).No.90 Rural Development and Panchayat
Raj(CGS.1) Department, Dated.07.05.2024.
 7. G.O.(Ms) No.93 Rural Development and Panchayat
Raj (CGS-1) Department, dated.22.05.2024
 8. Announcement made by Hon'ble Minister for Rural
Development Department on the floor of the
Tamil Nadu Legislative Assembly on 22.06.2024.

I invite your attention to the references cited.

In the reference 4th cited, Government of India, Ministry of Rural Development have approved Labour Budget of 20 Crore persondays under MGNREGS to Tamil Nadu for the financial year 2024-2025.

In the reference 5th cited, the Government of India have notified the wage rate for the FY 2024-25 as Rs.319/- per person per day in respect of Tamil Nadu. Government in the reference 7th cited has issued orders for the Rural Schedule of Rates for the year 2024-25 under MGNREGS.

In the reference 8th cited, the Hon'ble Minister for Rural Development has made the following Announcements on the floor of the Tamil Nadu Legislative Assembly 22.06.2024 during the Demand of Rural Development & Panchayat Raj Department as 12th Announcement.

I. ஊரக பகுதிகளில் 500 அரசு பள்ளிகளில் ரூ.100 கோடியில் சுற்றுச்சுவர் கட்டப்படும்.

மகாத்மா காந்தி தேசிய ஊரக வேலை உறுதித் திட்டத்தின் கீழ் ஊரகப் பகுதிகளில் உள்ள 500 அரசு பள்ளிகளுக்கு சுற்றுச் சுவர் கட்டும் பணி 100 கோடி ரூபாய் மதிப்பீட்டில் மேற்கொள்ளப்படும்

In the reference 1st cited, the Revised Schedule I of the National Rural Employment Guarantee Act, 2005 Paragraph 4 (1) IV Category-D: Rural Infra Structure provides "works for restoration of essential public infrastructure, the construction of Compound Wall for Government Schools as Community Asset is permitted

The construction of Compound wall to Government School Buildings in Rural area is a permitted activity as per Sl. No. 263 of Para 7.2.1 - "list of permissible works" under the **Annual Master Circular 2024-2025** of MGNREGA.

Construction of compound wall is approved by the Empowered Committee, Ministry of Rural Development, Government of India during the Empowered Committee Meeting held on 27.03.2024.

The above work were proposed by your District in the Shelf of Project of Labour Budget 2024-2025.

Hence, I request you to execute the construction of compound wall at an unit cost of Rs.78.45 lakhs per kilometre under MGNREGS as per the allocation and the guidelines. As per GoI guidelines, ceiling limit for the construction of Compound wall per school should not exceed Rs. 10 lakhs.

The District Collector should document various process of the Scheme implementation starting from selection of works to completion of works, documenting the works with photographs, video etc.,

Non-Negotiable Items:

1. Citizen Information Board shall be kept at the work site in 3 X 4 feet with all necessary information as per the framework given by the Government of India vide Ref No: k11023/1/1/2017 – MGNREGA (IV), MORD, Dated 07.04.2017. The cost of Citizen Information Board for community asset works will be fixed at **Rs.1,000/- per unit** and the cost of the Citizen information Board shall be included in the estimate itself. The CIB should only be wall painted for the works like Dugwells, Food Grain Godown, Milk Collection Centre, Culvert, and Minor Bridge etc.
2. Estimate creation, Administrative Sanction and Technical Sanction shall be done in SECURE software except for Convergence/Devolution Works.
3. Geo-Tagging of Assets at all three i.e before, during and after completion should be ensured.
4. In reference 5th cited, Ministry of Rural Development, Government of India have notified the wage rate and the Rural Schedule of Rates has been prepared accordingly for all the estimate preparation. In case of

any revision made in Rural Schedule of Rates in future, the same shall be adopted for the works.

5. Labour and material ratio of 60:40 should be ensured.


In addition to the above said guidelines, the following shall also be adhered to during the execution of works;

- Resolution should be obtained for in the Gram Sabha for all the Selected Works/Beneficiaries Selected and it should be entered work wise in Register No.2 of Mahatma Gandhi NREGA of village panchayats concerned.
- Photographs shall be taken before execution, during execution and after completion of work.

Hence, I request you to accord Administration Sanction from the proposed works in the Shelf of Project of Labour Budget 2024-2025 for the construction of School Compound wall in rural areas under MGNREGS during the FY 2024-2025.

I also request you to send the Administrative Sanction given details to this Directorate on or before 10.07.2024.

Encl:- Estimate.


Director

Copy to:


A. Lakshmi
27/6/24

1. The Principal Secretary to Government,
Rural Development & Panchayat Raj Department,
Secretariat, Chennai.
2. The Additional Collector (Dev.) / Project Director,
District Rural Development Agency,
All Districts.

1/2

Construction of Compound walls under Mahatma Gandhi NREGS for Government run Schools

DETAILED Cum ABSTRACT ESTIMATE (1000 m Length Wall)

							Est. Rs.	7845000
SL. No	Description	NO	Measurement			Qty	Amount	
			L	B	D			
1	Earth work excavation for foundation in all soils and sub - soils upto 0.30m depth as per SS20B for narrow foundations etc., complete as per standard specification.							
	For Column	350	0.90	0.90	0.30	85.05		
	Grade beam	1	1000.00	0.3	0.30	90.00		
	D/F Column	350	0.90	0.3	-0.30	-28.35		
	Total					146.70		
		146.70	cum	Rs	304.46	Cum	44664	
2	Earth work excavation for foundation in all soils and sub - soils t0.30m to 0.60 depth as per SS20B for narrow foundations etc., complete as per standard specification							
	For Column	350	0.90	0.9	0.30	85.05		
	Grade beam	1	1000.00	0.3	0.15	45.00		
	D/F Column	350	0.90	0.3	-0.15	-14.18		
	Total					115.88		
		131.29	cum	Rs	375.84	Cum	49344	
3	Earth work excavation for foundation in all soils and sub - soils above 0.60m depth as per SS20B for narrow foundations etc., complete as per standard specification							
	For Column	350	0.90	0.9	0.60	170.10		
	Total					170.10		
		170.10	cum	Rs	390.35	Cum	66399	
4	Supplying and filling in foundation and basement with Filling Sand in layers not more 15 cm thick etc., complete as per standard specification.							
	For Column	350	0.90	0.9	0.10	28.35		
	Grade beam	1	1000.00	0.3	0.10	30.00		
	D/F Column	350	0.90	0.3	-0.10	-9.45		
	Total					48.90		
		48.90	cum	Rs	1716.85	Cum	83954	
5	Cement Concrete 1:4:8 (One Cement Four sand and Eight Hard Broken Granite stone) using 40 mm gauge Hard Broken Granite stone jelly for foundation including cost and conveyance of all materials to site and all labour charges at site, including curing etc., complete as per standard specification.							
	For Column	350	0.90	0.9	0.10	28.35		
	Grade beam	1	1000.00	0.3	0.10	30.00		
	D/F Column	350	0.90	0.3	-0.10	-9.45		
	Total					48.90		
		48.90	cum	Rs	4937.75	Cum	241456	

SL. No	Description	NO			Measurement			Qty	Amount
					L	B	D		
6	Reinforced Cement concrete 1:11/2:3 mix using 20mm HBG metal for foundation and basement etc. complete as per standard specification.								
	Column pedal	350			0.90	0.9	0.15	42.53	
	Coping	350			(0.90+0.30)/2	(0.90+0.30)/2	0.30	37.80	
	Column base up to GL	350			0.23	0.23	0.50	9.26	
	Grade beam	1			1000.00	0.23	0.23	52.90	
	Column Superstructure	350			0.23	0.23	1.50	27.77	
	Total							170.26	
		170.26			cum	Rs	8363.06	Cum	1423853
7	Supplying and erecting centering of sides and soffits including supports and strutting up to 3.29m height for plane surfaces in all floors etc., complete as per standard specification.								
	Column up to GL	350			0.92	---	0.50	161.00	
	Beam 2 side	2			1000.00		0.23	460.00	
	Total							621.00	
		621.00			cum	Rs	476.50	Sqm	295907
	Column	350			0.92	---	1.50	483.00	
	Total							483.00	
		483.00			cum	Rs	953.00	Sqm	460299
8	Supplying and fabrication of steel including cost and conveyance of steel to site and all labour charges for straightening, cutting to length, bending to shape and tying in position and forming grills for all R.C.C works as per standard specification.								
	Column pedal 10mm dia	350	7	2	0.84		0.62	2551.92	
	Column 12mm dia	350	X	4	2.93		0.89	3650.78	
	Column 8mm dia stirups	350	X	17	0.84		0.39	1949.22	
	Grade beam 12mm dia	5			1000.00		0.89	4450.00	
	Grade beam 8mm dia stirups	665			0.84		0.39	217.85	
								12819.77	
		12.820			MT	Rs	88977.45		1140671
9	Brick work in cement Mortar 1:5 for super structure using Country brick etc., complete as per standard specification.								
	Superstructure	1			1000.00	0.23	0.30	69.00	
	Superstructure	1			1000.00	0.115	1.20	138.00	
	D/F column	350			0.23	0.23	-0.30	-5.55	
	D/F column	350			0.23	0.115	-1.20	-11.11	
	Total							190.34	

SL. No	Description	NO			Measurement			Qty	Amount
					L	B	D		
		190.34			m ³	Rs	5739.18	Cum	1092375
10	Plastering with C.M 1:5mix 12mm thich including cost and conveyance and all labour charges etc., complete as per standard specification.								
	Sides	1	X	2	1000.00		1.50	3000.00	
	Top	1			1000.00	0.115		115.00	
								3115.00	
		3115.00			m ²	Rs	238.59		743216
11	Colour washing Two coat with Plastic Emulsion Paint using best quality and approved variety of colour pigments including cost of all materials brushes and scaffolding charges etc. complete as per standard specification.								
		1	X	2	1000.00		1.50	3000.00	
	Top	1			1000.00	0.115		115.00	
								3115.00	
		3115.00			m ²	Rs	231.68	Sqm	721680
12	Towards Cost and Supply of Grill Gate including all charges etc.							LS	18000
							Sub Total	Rs.	6381817
13	GST	0.18							1014438
14	Price Escalation Cost 7%								446727
15	Provision For Citizen Information board.								1000
16	Photographic Charges							LS	1000
17	Contingencies and P.S. other charges etc.,							LS	18
	TOTAL Rs.								7845000

Director
Director

27/6/24
27/6/24

2/2

